

24th April, 2019

REF: GDC/MS/005/18-19/dk-maf

TO: ALL BIDDERS

Dear Sirs,

ADDENDUM 2: AMENDMENT & CLARIFICATION

RE: TENDER FOR SUPPLY OF WIGHBRIDGE & ACCESSORIES FOR MENENGAI GEOTHERMAL PROJECT – TENDER NO. GDC/DO/ICB/019/2018-2019

Following the Site Visit meeting held Pre-bid meeting held on 15th April, 2019, GDC wishes to clarify as follows;

No.	AMENDMENT & CLARIFICATION	
1.	<p>Item: CEMENT SILO SCALES On the site it was clarified that:-</p> <ul style="list-style-type: none"> - Installation services required will be 12 sets and not 6 as earlier clarified. 	<p>Installation services will be required for a total of 12 sets broken down as follows:</p> <ol style="list-style-type: none"> 1. Complete installation of load cells and indicators on 6 (six) silos 2. Replacement of weight indicators on 6 (six) silos with existing load cells to comply with requirements of the Department of Weights & Measures (<i>see Addendum 1 item 9</i>).
	<ul style="list-style-type: none"> - Calibration services will be 12 sets and not 6 as earlier clarified 	<p>Calibration services will be required for the 12 sets installed in items (1) and (2) above/schedule provided below.</p>
	<ul style="list-style-type: none"> - Verification and stamping will be for 12 sets and not 6 as earlier clarified 	<p>Verification and stamping will be required for the 12 sets installed in items (1) and (2) above/schedule provided below.</p>

<p>Item: HEAVY DUTY MODULAR WEIGHBRIDGES</p> <ul style="list-style-type: none"> - That the modular containerized weighbridge office/control room will be 1 unit and not 2 as indicated in addendum no 1 	<p>The modular containerized weighbridge office/control room shall be 2 units as indicated in addendum no 1. Each weighbridge shall be independent of the other.</p> <p>The networking of the 12 cement silos scales shall, however, be done to only one of the two weighbridge control rooms.</p>
<ul style="list-style-type: none"> - That telemetric system will be required to remotely monitor the cement tanks contents at any one given moment which was not explicitly clarified in the initial tender document nor in the addendum 1 issued 	<p>The 12 silos fitted with load cells shall be networked to the weighbridge control room complete with a separate panel for viewing the contents (weight) of each silo at any particular time to facilitate stock-take at a glance.</p>

HEAVY DUTY MODULAR WEIGHBRIDGE WITH OFFICE:

ITEM	SPECIFICATIONS	QTY
1.	Heavy duty modular Weighbridge & accessories	2
	Modular Containerized Weighbridge office/control room	2
	Weighbridge Installation	2
	Associated civil/fabrication works	2
	Supply, install, test and run software to GDC's satisfaction	2
	Supply, install, test and commission CCTV system	2
	Supply, install, test and commission biometric security	
	System for restricted access into the weigh house	2
	Automation works-RFID scanners and positioning sensors	
	For vehicle positioning on weigh bridge.	2
	Weighbridge Calibration	2
	Certified roller weights for calibration (10 tonnes)	1
	Training of 12 GDC staff	1
Verification and stamping by weights and measures	2	

CEMENT SILO SCALES

ITEM	SPECIFICATIONS	QTY
1.	Cement silo scale (load cells)	24pcs
	Weight Indicators (for silos with existing load cells)	6pcs
	Installation	12 sets
	Networking of silo weighing scales to weighbridge control room	1 lot
	Calibration	12 sets
	Training of 12 GDC staff	1
	Verification and stamping by weights and measures	12 sets

NB: All other instructions including the tender closing date of 30th April, 2019 at 1100HRS remain unchanged.

Yours faithfully,



DORIS KYAKA
MANAGER, SUPPLY CHAIN
FOR: GEOTHERMAL DEVELOPMENT COMPANY

